



Roof Replacement Estimate

PROPERTY

1261 20th St, Newport News, VA 23607, USA

ROOF AREA	PITCH	MATERIAL
2,530 sqft	4:12	GAF Timberline HDZ
WARRANTY	WIND RATING	TEAR-OFF
Lifetime ltd	130 mph	Single layer

Scope of work

Complete tear-off of existing roofing material with full deck inspection. Install GAF Timberline HDZ field shingles, matched starter strip, and hip & ridge cap shingles; new synthetic underlayment over the entire deck and ice & water shield at all eaves and valleys. New aluminum drip edge along eaves and rakes, W-valley metal in all valleys, and step + counter flashing at sidewalls and chimneys. New pipe boots on all plumbing vents and a continuous ridge vent. Permits, inspections, dumpster, site protection, daily cleanup, and a final magnetic sweep are included.

Materials	\$11,006
Labor	\$13,756
Disposal & permit	\$1,020
Total	\$25,782

Terms

Validity: 30 days from date above. **Warranty:** manufacturer warranty per product spec (Lifetime ltd); 5-year workmanship warranty from completion. **Payment:** 30% deposit at signing, 40% on tear-off, 30% on completion. Insurance jobs may follow ACV/RCV release schedule. **Scope changes:** decking replacement or hidden damage discovered during tear-off will be quoted as change orders before work proceeds.

Customer signature

Date

Contractor representative

Date



Materials

Item	Qty	Rate	Amount
Architectural field shingles (15% waste)	29.1 sq	\$169.23	\$4923.77
Starter strip	323 lf	\$1.69	\$546.62
Hip & ridge cap shingles	216 lf	\$6.92	\$1495.38
Synthetic underlayment	2530 sqft	\$0.31	\$778.46
Ice & water shield (eaves + valleys)	570 sqft	\$0.92	\$526.15
Drip edge (aluminum, eaves + rakes)	323 lf	\$1.69	\$546.62
Valley metal (W-valley)	63 lf	\$5.38	\$339.23
Step flashing	22 pc	\$1.85	\$40.62
Counter flashing	22 lf	\$6.92	\$152.31
Box vent assemblies (replace existing)	2 ea	\$43.08	\$86.15
Roofing nails (1.25" galv)	29.1 sq	\$6.92	\$201.43
Continuous ridge vent	180 lf	\$6.92	\$1246.15
Sealants & consumables	1 job	\$123.08	\$123.08
Materials			\$11,006

Labor

Item	Qty	Rate	Amount
Tear-off (single-layer)	2530 sqft	\$1.00	\$2530.00
Install field shingles + underlayment + starter	2530 sqft	\$2.31	\$5838.46
Ice & water shield install	570 sqft	\$0.62	\$350.77
Hip / ridge cap install	216 lf	\$4.62	\$996.92
Valley install (with metal)	63 lf	\$7.69	\$484.62
Drip edge install	323 lf	\$1.54	\$496.92
Step flashing install	22 pc	\$6.92	\$152.31
Counter flashing install	22 lf	\$8.46	\$186.15
Box vent install	2 ea	\$53.85	\$107.69
Ridge vent install	180 lf	\$4.62	\$830.77
Site cleanup + magnetic sweep	1 job	\$307.69	\$307.69
Labor			\$13,756