



Roof Replacement Estimate

PROPERTY

1612 S Canton Ave, Springfield, MO 65802, USA

ROOF AREA	PITCH	MATERIAL
2,757 sqft	7:12	GAF Timberline HDZ
WARRANTY	WIND RATING	TEAR-OFF
Lifetime ltd	130 mph	Single layer

Scope of work

Complete tear-off of existing roofing material with full deck inspection. Install GAF Timberline HDZ field shingles, matched starter strip, and hip & ridge cap shingles; new synthetic underlayment over the entire deck and ice & water shield at all eaves and valleys. New aluminum drip edge along eaves and rakes, W-valley metal in all valleys, and step + counter flashing at sidewalls and chimneys. New pipe boots on all plumbing vents and a continuous ridge vent. Permits, inspections, dumpster, site protection, daily cleanup, and a final magnetic sweep are included.

Materials	\$8,144
Labor	\$9,567
Disposal & permit	\$1,020
Total	\$18,731

Terms

Validity: 30 days from date above. **Warranty:** manufacturer warranty per product spec (Lifetime ltd); 5-year workmanship warranty from completion. **Payment:** 30% deposit at signing, 40% on tear-off, 30% on completion. Insurance jobs may follow ACV/RCV release schedule. **Scope changes:** decking replacement or hidden damage discovered during tear-off will be quoted as change orders before work proceeds.

Customer signature

Date

Contractor representative

Date



Materials

Item	Qty	Rate	Amount
Architectural field shingles (15% waste)	31.71 sq	\$157.14	\$4982.29
Starter strip	99 lf	\$1.57	\$155.57
Hip & ridge cap shingles	134 lf	\$6.43	\$861.43
Synthetic underlayment	2757 sqft	\$0.29	\$787.71
Ice & water shield (eaves + valleys)	348 sqft	\$0.86	\$298.29
Drip edge (aluminum, eaves + rakes)	99 lf	\$1.57	\$155.57
Valley metal (W-valley)	28 lf	\$5.00	\$140.00
Step flashing	22 pc	\$1.71	\$37.71
Counter flashing	22 lf	\$6.43	\$141.43
Box vent assemblies (replace existing)	2 ea	\$40.00	\$80.00
Roofing nails (1.25" galv)	31.71 sq	\$6.43	\$203.81
Continuous ridge vent	51 lf	\$6.43	\$327.86
Sealants & consumables	1 job	\$114.29	\$114.29
Materials			\$8,144

Labor

Item	Qty	Rate	Amount
Tear-off (single-layer)	2757 sqft	\$0.93	\$2560.07
Install field shingles + underlayment + starter	2757 sqft	\$2.14	\$5907.86
Ice & water shield install	348 sqft	\$0.57	\$198.86
Hip / ridge cap install	134 lf	\$4.29	\$574.29
Valley install (with metal)	28 lf	\$7.14	\$200.00
Drip edge install	99 lf	\$1.43	\$141.43
Step flashing install	22 pc	\$6.43	\$141.43
Counter flashing install	22 lf	\$7.86	\$172.86
Box vent install	2 ea	\$50.00	\$100.00
Ridge vent install	51 lf	\$4.29	\$218.57
Site cleanup + magnetic sweep	1 job	\$285.71	\$285.71
Labor			\$9,567