



Roof Replacement Estimate

PROPERTY

3561 E 102nd Ct, Thornton, CO 80229, USA

ROOF AREA	PITCH	MATERIAL
2,081 sqft	9:12	GAF ArmorShield II
WARRANTY	WIND RATING	TEAR-OFF
Lifetime ltd	130 mph	Single layer

Scope of work

Complete tear-off of existing roofing material with full deck inspection. Install GAF ArmorShield II field shingles, matched starter strip, and hip & ridge cap shingles; new synthetic underlayment over the entire deck and ice & water shield at all eaves and valleys. New aluminum drip edge along eaves and rakes, W-valley metal in all valleys, and step + counter flashing at sidewalls and chimneys. New pipe boots on all plumbing vents and a continuous ridge vent. Permits, inspections, dumpster, site protection, daily cleanup, and a final magnetic sweep are included.

Materials	\$11,517
Labor	\$16,136
Disposal & permit	\$880
Total	\$28,533

Insurance & rebate notes

Class 4 hail discount (CO)

Colorado homeowner's insurance carriers offer a 10–30% premium discount for UL 2218 Class 4 impact-resistant shingles. With the Front Range's hail frequency, insurers actively reward upgrading — and sometimes require it. *(On a typical \$2,800/yr premium, a 20% discount saves about \$560/yr. The Class 4 upgrade typically pays itself back in 4–7 years.)*

Next step: Bring the Class 4 manufacturer certification to your insurance agent for the file. Ask about non-renewal protection — most Class 4 policies include it.

Terms

Validity: 30 days from date above. **Warranty:** manufacturer warranty per product spec (Lifetime ltd); 5-year workmanship warranty from completion. **Payment:** 30% deposit at signing, 40% on tear-off, 30% on completion. Insurance jobs may follow ACV/RCV release schedule. **Scope changes:** decking replacement or hidden damage discovered during tear-off will be quoted as change orders before work proceeds.

Customer signature

Date

Contractor representative

Date



Materials

Item	Qty	Rate	Amount
Class 4 Impact field shingles (15% waste)	23.93 sq	\$291.67	\$6980.02
Starter strip	132 lf	\$1.83	\$242.00
Hip & ridge cap shingles	117 lf	\$7.50	\$877.50
Synthetic underlayment	2081 sqft	\$0.33	\$693.67
Ice & water shield (eaves + valleys)	531 sqft	\$1.00	\$531.00
Drip edge (aluminum, eaves + rakes)	132 lf	\$1.83	\$242.00
Valley metal (W-valley)	45 lf	\$5.83	\$262.50
Step flashing	22 pc	\$2.00	\$44.00
Counter flashing	22 lf	\$7.50	\$165.00
Pipe boots (rubber)	2 ea	\$23.33	\$46.67
Box vent assemblies (replace existing)	2 ea	\$46.67	\$93.33
Roofing nails (1.25" galv)	23.93 sq	\$7.50	\$179.48
Continuous ridge vent	50 lf	\$7.50	\$375.00
Sealants & consumables	1 job	\$133.33	\$133.33
Materials			\$11,517

Labor

Item	Qty	Rate	Amount
Tear-off (single-layer)	2081 sqft	\$1.08	\$2254.42
Install field shingles + underlayment + starter	2081 sqft	\$2.50	\$5202.50
Ice & water shield install	531 sqft	\$0.67	\$354.00
Hip / ridge cap install	117 lf	\$5.00	\$585.00
Valley install (with metal)	45 lf	\$8.33	\$375.00
Drip edge install	132 lf	\$1.67	\$220.00
Step flashing install	22 pc	\$7.50	\$165.00
Counter flashing install	22 lf	\$9.17	\$201.67
Vent boot install	2 ea	\$58.33	\$116.67
Box vent install	2 ea	\$58.33	\$116.67
Ridge vent install	50 lf	\$5.00	\$250.00
Site cleanup + magnetic sweep	1 job	\$333.33	\$333.33
Labor			\$16,136