



Roof Replacement Estimate

PROPERTY

3820 E Rosebrier St, Springfield, MO 65809, USA

ROOF AREA	PITCH	MATERIAL
5,566 sqft	6:12	GAF Timberline HDZ
WARRANTY	WIND RATING	TEAR-OFF
Lifetime ltd	130 mph	Single layer

Scope of work

Complete tear-off of existing roofing material with full deck inspection. Install GAF Timberline HDZ field shingles, matched starter strip, and hip & ridge cap shingles; new synthetic underlayment over the entire deck and ice & water shield at all eaves and valleys. New aluminum drip edge along eaves and rakes, W-valley metal in all valleys, and step + counter flashing at sidewalls and chimneys. New pipe boots on all plumbing vents and a continuous ridge vent. Permits, inspections, dumpster, site protection, daily cleanup, and a final magnetic sweep are included.

Materials	\$15,947
Labor	\$18,488
Disposal & permit	\$1,180
Total	\$35,615

Terms

Validity: 30 days from date above. **Warranty:** manufacturer warranty per product spec (Lifetime ltd); 5-year workmanship warranty from completion. **Payment:** 30% deposit at signing, 40% on tear-off, 30% on completion. Insurance jobs may follow ACV/RCV release schedule. **Scope changes:** decking replacement or hidden damage discovered during tear-off will be quoted as change orders before work proceeds.

Customer signature

Date

Contractor representative

Date



Materials

Item	Qty	Rate	Amount
Architectural field shingles (20% waste)	66.79 sq	\$157.14	\$10495.88
Starter strip	140 lf	\$1.57	\$220.00
Hip & ridge cap shingles	238 lf	\$6.43	\$1530.00
Synthetic underlayment	5566 sqft	\$0.29	\$1590.29
Ice & water shield (eaves + valleys)	585 sqft	\$0.86	\$501.43
Drip edge (aluminum, eaves + rakes)	140 lf	\$1.57	\$220.00
Valley metal (W-valley)	55 lf	\$5.00	\$275.00
Step flashing	22 pc	\$1.71	\$37.71
Counter flashing	22 lf	\$6.43	\$141.43
Pipe boots (rubber)	3 ea	\$20.00	\$60.00
Box vent assemblies (replace existing)	4 ea	\$40.00	\$160.00
Roofing nails (1.25" galv)	66.79 sq	\$6.43	\$429.37
Continuous ridge vent	70 lf	\$6.43	\$450.00
Sealants & consumables	1 job	\$114.29	\$114.29
Materials			\$15,947

Labor

Item	Qty	Rate	Amount
Tear-off (single-layer)	5566 sqft	\$0.93	\$5168.43
Install field shingles + underlayment + starter	5566 sqft	\$2.14	\$11927.14
Ice & water shield install	585 sqft	\$0.57	\$334.29
Hip / ridge cap install	238 lf	\$4.29	\$1020.00
Valley install (with metal)	55 lf	\$7.14	\$392.86
Drip edge install	140 lf	\$1.43	\$200.00
Step flashing install	22 pc	\$6.43	\$141.43
Counter flashing install	22 lf	\$7.86	\$172.86
Vent boot install	3 ea	\$50.00	\$150.00
Box vent install	4 ea	\$50.00	\$200.00
Ridge vent install	70 lf	\$4.29	\$300.00
Site cleanup + magnetic sweep	1 job	\$285.71	\$285.71
Labor			\$18,488