



Roof Replacement Estimate

PROPERTY

3820 E Rosebrier St, Springfield, MO 65809, USA

ROOF AREA	PITCH	MATERIAL
5,566 sqft	6:12	GAF Timberline HDZ
WARRANTY	WIND RATING	TEAR-OFF
Lifetime ltd	130 mph	Single layer

Scope of work

Complete tear-off of existing roofing material with full deck inspection. Install GAF Timberline HDZ field shingles, matched starter strip, and hip & ridge cap shingles; new synthetic underlayment over the entire deck and ice & water shield at all eaves and valleys. New aluminum drip edge along eaves and rakes, W-valley metal in all valleys, and step + counter flashing at sidewalls and chimneys. New pipe boots on all plumbing vents and a continuous ridge vent. Permits, inspections, dumpster, site protection, daily cleanup, and a final magnetic sweep are included.

Materials	\$15,947
Labor	\$18,488
Disposal & permit	\$1,180
Total	\$35,615

Terms

Validity: 30 days from date above. **Warranty:** manufacturer warranty per product spec (Lifetime ltd); 5-year workmanship warranty from completion. **Payment:** 30% deposit at signing, 40% on tear-off, 30% on completion. Insurance jobs may follow ACV/RCV release schedule. **Scope changes:** decking replacement or hidden damage discovered during tear-off will be quoted as change orders before work proceeds.

Customer signature

Date

Contractor representative

Date