



Roof Replacement Estimate

PROPERTY

6310 Laguna Bay Ct, Houston, TX 77041, USA

ROOF AREA	PITCH	MATERIAL
4,186 sqft	8:12	GAF ArmorShield II
WARRANTY	WIND RATING	TEAR-OFF
Lifetime ltd	130 mph	Single layer

Scope of work

Complete tear-off of existing roofing material with full deck inspection. Install GAF ArmorShield II field shingles, matched starter strip, and hip & ridge cap shingles; new synthetic underlayment over the entire deck and ice & water shield at all eaves and valleys. New aluminum drip edge along eaves and rakes, W-valley metal in all valleys, and step + counter flashing at sidewalls and chimneys. New pipe boots on all plumbing vents and a continuous ridge vent. Permits, inspections, dumpster, site protection, daily cleanup, and a final magnetic sweep are included.

Materials	\$17,382
Labor	\$17,604
Disposal & permit	\$1,180
Total	\$36,166

Insurance & rebate notes

Class 4 wind/hail discount (TX)

Texas mandates that home insurance carriers file a discount for UL 2218 Class 4 impact-resistant shingles. Most carriers in TX (including State Farm, Allstate, Farmers, USAA) discount the wind/hail portion of your premium between 15% and 30% — most landing at 20–25%. *(On a typical \$3,500/yr premium where roughly 60% is wind/hail coverage, a 25% discount saves about \$525/yr. That recovers the upgrade-from-architectural cost in ~5 years and continues to save you money every year after.)*

Next step: Call your insurance agent before we schedule the job. Ask for the exact discount percentage and whether they need a shingle-wrapper photo or just the manufacturer's Class 4 certification for the file.

Terms

Validity: 30 days from date above. **Warranty:** manufacturer warranty per product spec (Lifetime ltd); 5-year workmanship warranty from completion. **Payment:** 30% deposit at signing, 40% on tear-off, 30% on completion. Insurance jobs may follow ACV/RCV release schedule. **Scope changes:** decking replacement or hidden damage discovered during tear-off will be quoted as change orders before work proceeds.

Customer signature

Date

Contractor representative

Date



Materials

Item	Qty	Rate	Amount
Class 4 Impact field shingles (15% waste)	48.14 sq	\$257.35	\$12388.70
Starter strip	148 lf	\$1.62	\$239.41
Hip & ridge cap shingles	200 lf	\$6.62	\$1323.53
Synthetic underlayment	4186 sqft	\$0.29	\$1231.18
Ice & water shield (eaves + valleys)	525 sqft	\$0.88	\$463.24
Drip edge (aluminum, eaves + rakes)	148 lf	\$1.62	\$239.41
Valley metal (W-valley)	27 lf	\$5.15	\$138.97
Step flashing	22 pc	\$1.76	\$38.82
Counter flashing	22 lf	\$6.62	\$145.59
Pipe boots (rubber)	3 ea	\$20.59	\$61.76
Roofing nails (1.25" galv)	48.14 sq	\$6.62	\$318.57
Continuous ridge vent	66 lf	\$6.62	\$436.76
Sealants & consumables	1 job	\$117.65	\$117.65
Materials			\$17,382

Labor

Item	Qty	Rate	Amount
Tear-off (single-layer)	4186 sqft	\$0.96	\$4001.32
Install field shingles + underlayment + starter	4186 sqft	\$2.21	\$9233.82
Ice & water shield install	525 sqft	\$0.59	\$308.82
Hip / ridge cap install	200 lf	\$4.41	\$882.35
Valley install (with metal)	27 lf	\$7.35	\$198.53
Drip edge install	148 lf	\$1.47	\$217.65
Step flashing install	22 pc	\$6.62	\$145.59
Counter flashing install	22 lf	\$8.09	\$177.94
Vent boot install	3 ea	\$51.47	\$154.41
Ridge vent install	66 lf	\$4.41	\$291.18
Site cleanup + magnetic sweep	1 job	\$294.12	\$294.12
Labor			\$17,604